Serial No.	Particulars.	Number.	Value. Rs. a. p.
	Lot :—29 :—		
99.	5″ W. I. bend with collar	1	
100.	5″ G. I. Tee	1	
104.	4″ W. I. nipple	1	
	Lot—30 :—		
114.	Cone spanners for deep well pump brass barrel	5	
	Lot—31 :—Sundries including items 159, 160, 161, 167, 171, 181, 208, 209.		
	Lot—32 :—		
275.	Assorted articles, such as unfinished blanks and used gears		
	Lot—33 :—Sundries included in items numbers 305 (*a*), (*c*), (*d*), (*e*), (*f*)		
	Lot—34 :—Sundries included in items numbers 306 (*a*), (*b*), (*c*), (*d*), (*e*), (*f*), (*g*), (*h*) and 325 (*b*).		
130.	(*a*) New radiator useful for soap factory	1	
326.	Lot—35 :—*Belt pulleys* :—		
	(1) 4′ dia. belt pulley width of face 5″	1	
	(2) 1′ dia. belt pulley	1	
166.	Gas stove made of copper	1	
144.	1 spare hand wheel belonging to deep well pump	1	
325.	(*a*) bleeder.		

III.

List of articles (raw materials) to be auctioned off from stores.

Sl. No.	Particulars	Number	Value Rs. a. p.
1.	Galvanized iron screws (one bag)	85 lbs.	14 10 10
2.	Crossovell steel	Cwt. 0—14—0—9	1,102 12 5
3.	Nickle steel round and square	„ 0—3—0—7	34 11 3
4.	Acid Tool steel for bullock cart tyres	8	49 6 1
5.	Asbestos sheet 4′×4′×¼″	5—3—11¼ lbs.	302 13 11
6.	Expanded metal 5½ rolls	..	48 4 5
7.	5″×½″ m.s. flats 18 feet—18 bars	..	..
8.	Cupoloa turned into sheets	Cwts. 15—0—0	44 12 0
9.	4″ brass pipe No. 1	„ 1—3—10	140 0 0
10.	2½″ brass pipe No. 1		
11.	White metal ordinary	„ 2—1—12¼	56 7 3
12.	2½″×⅝″ m. s. flats		
13.	Bamboos	4	
14.	⅝″ pegs	4	
15.	Sign Boards	7	

B. G. APPADORAI MUDALIAR,
Superintendent,
Central Industrial Workshop,
Bangalore.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Abstract Notification dated 22nd February 1939.

The attention of the public is invited to the notification callig for tenders for the work of 'Sinking a curbwell of 16 ft. diameter and 30 ft. depth for water supply to Sagar Town,' published in pages 415-416, Part VI of the *Mysore Gazette*, dated 2nd March 1939.

The last date for receipt of tenders is on 17th March 1939.

Notification dated 6th March 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 20th March 1939, for constructing slaughterhouse in Nanjangud town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 192 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing slaughterhouse in Nanjangud town," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for the work of Constructing a slaughterhouse in Nanjargud Town.

No.	Items of work	Unit	Rate	Quantity	Total
			Rs. a. p.		Rs.
1	Earthwork, excavating the foundation and filling in basement	C.yd.	..	39	
2	Burnt size stone in mud for filling foundation and basement	C.ft.	..	1,436	
3	Burnt brick in clay for superstructure	C.ft.	..	1,611	
4	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	..	67	
5	Do 3″ thick for coping roughly dressed and fixed	,,	..	19	
6	Burnt brick in lime mortar	C.ft.	..	32	
7	Providing and fixing teakwood door with 3″×4″ frame, 1″ thick battened shutters including iron fittings, etc., complete	S.ft.	..	46	
8	Teakwood windows with 1″ thick battened shutters outside and ¾″ diameter iron rods in the middle, fly-proof wire gauze shutters inside including necessary iron fittings, etc., complete	S.ft.	..	20	
9	Providing and fixing reinforced cement concrete ventilators as per approved design	,,	..	21	
10	Roofing with reinforced burnt brick cement concrete and finshing with surki concrete and two courses of flat tiles, etc., complete	Sqrs.	..	5·45	
11	Providing and fixing steel girders including painting etc., complete	Cwt.	..	5·78	
12	Flooring with 1½″ cement concrete in the proportion of 1:2:4 on 3″ thick lime concrete of stone jelly and plastering the surface with cement plastering in the proportion of 1:3 etc., complete	Sqr.	..	6·51	
13	Plastering with ½″ cement mortar in the proportion of 1:3	,,	..	10·51	
14	Plastering with ½″ thick lime mortar	,,	..	24·39	
15	Providing and fixing a wicket gate of approval design with necessary iron fittings	S.ft.	..	15	

No.	Items of work	Unit	Rate	Quantity	Total
			Rs. a. p.		Rs.
16	Constructing parapet wall 4½″ thick and 9″ high with burnt brick in lime mortar over terrace roofing including plastering, white-washing, etc., complete as per design	R.ft.	..	112	
17	Constructing coping over 9″ brick walls with burnt brick in lime mortar and white-washing, etc., complete as per design	,,	..	115	
18	White or colour washing, two coats	Sqr.	..	24·39	
19	Silicate painting of required colour, two coats ..	,,	..	1·32	
20	Constructing gutting platform with brick in clay and cement plastering, etc., complete	No.	..	1	
21	Cement pointing to basement	Sqr.	..	2·00	
22	Constructing 4″ U shaped drain with cement concrete and cement plastering, etc., complete	R.ft.	..	32	
23	Constructing blood pool cistern with brick in cement mortar over cement concrete bed and cement plastering the exposed surface, etc., complete ..	No.	..	2	
24	Providing and fixing 6″×4″ S.W. gully trap in cement concrete and constructing cistern with brick in cement mortar and cement plastering, etc., complete including supplying and fixing 9″×12″ hinged lid and frame	No.	..	1	
25	Supplying and laying and jointing 4″ S.W. pipe of approved quality with hemp caulking and cement mortar including earthwork excavating, refilling the trench, barricading, lighting, shoring sides, employing watchman in the nights and testing the line with water, etc., complete	R.ft.	..	24	
26	Constructing septic tank 5′×3′×4′ with 1 foot cement concrete for bed, brick in cement mortar for walls alround 9″ thick, ½″ cement plastering (1 : 3), covering with 6″ thick burnt stone slabs including the provision of C.I. manhole cover 21″ diameter and frame with steps, complete with earthwork excavation and filling, etc.	No.	..	1	
27	Constructing soakage pit 6′×4′×8′, earthwork excavation filling with boulders of different size and covering the top with small jelly including providing of loose S.W. pipes, etc., complete	No.	..	1	
28	Providing expanded metal of required mesh for open yard with 2″ angle iron verticals of 6 feet high and inserted in the masonry	S.ft.	..	308	

N. KRISHNIENGAR,
Sanitary Engineer.

OFFICE OF THE PALACE ENGINEER, MARAMATH DEPARTMENT, MYSORE.

Abstract Notification dated 23rd February 1939.

The attention of the public is invited to the advertisement on pages 418-419 of Part VI of the ***Mysore Gazette***, dated 2nd March 1939, calling for tenders for "Constructing the 14th Line of Family Houses at Body Guards, Mysore."

———

Abstract Notification dated 27th February 1939.

The attention of the public is invited to the advertisement on pages 440-442 of Part VI of the ***Mysore Gazette***, dated 2nd March 1939, calling for tenders for "Constructing a permanent portico to the North side of Palace in front of Drawing Room," Mysore.

A. SESHAPPA,
For *Palace Engineer.*